

Owner
CELEBRITY WESTCHESTER REALTY, LLC
5 ANDERSON LANE
GOLDENS BRIDGE, NY 10526

Planning Administrator
CIORS DAN CONRAN
79 BOUTON ROAD
SOUTH SALEM, NY 10590

Reviewed for compliance with the Planning Board Resolution No. 10-1 dated 03/17/2020.

	PROPERTY LINE		PROPOSED FINISHED GRADE
	ADJACENT PROPERTY LINE		PROPOSED SPOT GRADE
	EXISTING BUILDING LINE		PROPOSED DRAINAGE MANHOLE
	EXISTING PAVEMENT EDGE OR CURB LINE		PROPOSED DRAIN INLET, TYPE CI & DI
	EXISTING FENCE		PROPOSED STORM LINE & SIZE
	EXISTING OVERHEAD WIRE		PROPOSED SEWAGE SYSTEM STRUCTURES
	EXISTING STONE WALL		PROPOSED SANITARY FORCE MAIN
	EXISTING RETAINING WALL		DOUBLE DRAIN INLET
	EXISTING LIGHT STANDARD		TRENCH DRAIN
	EXISTING UTILITY POLE		PROPOSED CONCRETE CURB
	EXISTING ROOK LEDGE		PROPOSED SOLID WOOD FENCE
	EXISTING SPOT GRADE		PROPOSED BUILDING LINE
	EXISTING MANHOLE		PROPOSED BUILDING OVERHANG
	EXISTING DRAIN INLET		PROPOSED N.Y.S.D.O.T. CONCRETE CURB
	EXISTING WRECK CONTOUR		PROPOSED MONOLITHIC CURB & SIDEWALK
	EXISTING MINOR CONTOUR		PROPOSED STANDARD PARKING SPACES WITH NUMBER OF SPACES AND TYPE INDICATED
	APPROXIMATE EXISTING GS INDEX CONTOUR		TRAFFIC SIGN LOCATION & DESIGNATION
	APPROXIMATE EXISTING GS MINOR CONTOUR		PROPOSED RETAINING WALL
			18" WIDE WHITE STOP LINE WITH DOUBLE YELLOW LINE
			ARROW MARKING ON PAVEMENT
			PROPOSED LIGHT STANDARDS
			PROPOSED, RELOCATED UTILITY POLE
			PROPOSED WHITE PRIVACY PVC FENCE
			STONE & BLOCK DROP INLET PROTECTION
			SILT FENCE
			PROPOSED LIMIT OF DISTURBANCE
			SILT SACK INLET PROTECTION
			STABILIZED CONSTRUCTION ENTRANCE

4. ALL SEEDMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH ALL THE PLANS, PRIOR TO BEGINNING ANY CLEARING.
5. SILT FENCE SHALL BE INSTALLED AS SHOWN ON THIS DRAWING PRIOR TO BEGINNING ANY GRADING.
6. EXPOSED SLOPES AND ALL GRADING SHALL BE SEED SOON WITH THE FOLLOWING GRASS MIX IMMEDIATELY UPON COMPLETION OF ITS CONSTRUCTION AT A RATE OF 100 LBS PER 1000 SQ YD. THE FOLLOWING PROPORTIONS:

OSPREY PINE FESCUE	30%
PERMANENT BERMUDGRASS	30%
GRASS SEED MIX	40%
7. GRASS SEED MIX FOR SEEDMENT AND EROSION CONTROL MAY BE APPLIED BY EITHER MECHANICAL OR HYDROSEEDING METHODS. HYDROSEEDING SHALL BE PERFORMED IN ACCORDANCE WITH THE HYDROSEEDING SPECIFICATIONS FOR A STANDARD BARRIERS FOR NURSERY STOCK, LATEST EDITION.
8. SEEDED AREAS SHALL BE MULCHED WITH STRAW AT A RATE OF 2 TONS PER 1000 SQ YD.
9. SEEDMENT AND EROSION CONTROL MEASURES SHALL BE INSPECTED AND MAINTAINED ON A DAILY BASIS BY THE CONTRACTOR. ALL COLLECTED SEDIMENT WITHIN 24 HOURS SHALL BE REMOVED FROM THE SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FUNCTION OF THE SEDIMENT BARRIER. ALL SEDIMENT COLLECTED SHALL BE RESPIRABLE AND NON-TOXIC TO THE ENVIRONMENT.
10. DUST SHALL BE CONTROLLED BY SPRINKLING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE ADJOURNING PROPERTIES.
11. WATER CANNOT BE USED TO CONTROL ADJOURNING PROPERTIES, NOR DIVERST CUTO INTO THE PROPERTY OF OTHERS.
12. ALL FILLS SHALL BE COMPACTED TO PROVIDE STABILITY OF MATERIAL AND TO PREVENT EROSION OF FILLS.
13. EXCAVATIONS AND FILLS SHALL BE ROLLED, SEADED AND STABILIZED AT COMPLETION OF EACH CONSTRUCTION DAY, UNLESS OTHERWISE SPECIFIED.
14. THE CONTRACTOR SHALL MAINTAIN RECORDS OF ALL EVIDENCE OF SEDIMENTATION ON A WEEKLY BASIS AND AFTER RAINSTORMS.
15. AS WARRANTED BY FIELD CONDITIONS, SPECIAL, ADDITIONAL, SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED AS NECESSARY TO PREVENT SEDIMENTATION.
16. STOPPING OF CONSTRUCTION MATERIAL SHALL BE PLACED ON-SITE IN THE AREAS DESIGNATED. STOPPED EXCAVATION MATERIAL SHALL HAVE SILT FENCE OR OTHER EROSION CONTROL MEASURES INSTALLED TO PREVENT SEDIMENTATION IN AN ORDERLY MANNER SO AS NOT TO INTERFERE ON EXISTING TRAFFIC CIRCULATION ROUTES.
17. THIS PLAN IS FOR PHASING AND SEDIMENT AND EROSION CONTROL INFORMATION ONLY. IF SOIL STOPPAGE AREA WILL NOT BE USED FOR AN EXTENDED PERIOD OF TIME, THE AREA SHALL BE RESEEDED AND STABILIZED.
18. SCHEDULE OF BLASTING SHALL BE FINALIZED WHEN CONSTRUCTION DOCUMENTS ARE SUBMITTED AND SURFACE INVESTIGATION IS CONDUCTED TO DETERMINE EXISTING COORDINATE AND DEPTH OF UNDERGROUND UTILITY.

1. EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEEN TAKEN FROM SURVEY TITLE "TOPOGRAPHIC SURVEY OF PROPERTY," PREPARED BY INSITE ENGINEERING, SURVEYING PROFESSIONAL CORPORATION, P.C., DATED 08/17/2007, RECORDED 09/04/2007.
2. PRIOR TO THE START AND/OR DEMOLITION, THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND/OR APPROVALS FROM THE TOWNS OF LEWISBORO AND ALL OTHER AUTHORITIES HAVING JURISDICTION.
3. ALL CONSTRUCTION/DEMOLITION DERIVED NOT PROPOSED TO BE RECYCLED SHALL BE PROPERLY AND LEGALLY DEPOSITED IN A MANNER IN ACCORDANCE WITH THE REGULATION OF ALL LOCAL, STATE AND FEDERAL AGENCIES HAVING JURISDICTION.
4. ALL MATERIAL TO BE USED AS FILL SHALL BE APPROVED BY THE PROJECT CONSULTANT.
5. PRIOR TO THE START OF SITE DEMOLITION, EROSION AND SEDIMENT CONTROL DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH THE NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL, AS REQUIRED AND/OR DIRECTED BY THE PROJECT CONSULTANT.
6. ANY UNDESIRABLE MATERIAL FOUND ON-SITE DURING CONSTRUCTION SHALL BE DISPOSED OF OFF-SITE IN A MANNER APPROVED BY ALL AUTHORITIES HAVING JURISDICTION AND SHALL BE REMOVED FROM THE PROJECT SITE. UNDESIRABLE MATERIAL SHALL BE REMOVED FROM THE PROJECT SITE AND SHALL BE COMPLETED UNDER THE DIRECT SUPERVISION OF A GEOTECHNICAL ENGINEER.
7. EXISTING DRAINAGE PATTERNS ON SITE SHALL BE MAINTAINED TO THE MAXIMUM EXTENT POSSIBLE.
8. THESE PLANS ARE TO BE PROVIDED TO THE DEMOLITION CONTRACTOR AND SITE CONTRACTOR FOR THEIR USE, INFORMATION AND COORDINATION. ANY QUESTIONS OR DISCREPANCIES SHOULD BE IMMEDIATELY REPORTED TO THE DESIGNER. IT SHALL BE THE GENERAL CONTRACTOR IN WRITING PRIOR TO ISSUANCE OF BID.
9. CONTRACTOR SHALL VERIFY THE LOCATION OF EXISTING UTILITIES TO BE DEMOLISHED AND EXISTING UTILITIES TO BE PROTECTED. IF ANY DISCREPANCIES ARE FOUND, THE CONTRACTOR SHALL NOTIFY THE GENERAL CONTRACTOR AND PRIOR TO THE START OF CONSTRUCTION.
10. ALL SANITARY SEWER AND WATER UTILITIES THAT MUST BE REMOVED AND/OR RELOCATED SHALL BE COMPLETED IN ACCORDANCE WITH WESTCHESTER COUNTY HEALTH DEPARTMENT RULES AND REGULATIONS.
11. ERM WETLANDS REQUIREMENT SPECIFIED IN PART 1.0, 1.1, 1.2 OF THE SPDES GENERAL PERMITS (9-01-05-002) MUST BE ADDRESSED TO RELEVANT SUB-STATELIZATION FOR EAST

[illegible]

EROSION AND SEDIMENT CONTROL MEASURE	INSPECTION/MAINTENANCE INTERVALS	INSPECTION/MAINTENANCE REQUIREMENTS
STABILIZED CONSTRUCTION ENTRANCE	DAILY	<ul style="list-style-type: none"> PERIODIC TOP DRESSING WITH ADDITIONAL AGGREGATE AS REQUIRED TO MAINTAIN IN PUBLIC ROADWAYS IMMEDIATELY
SILT FENCE	DAILY AFTER EACH RAIN	<ul style="list-style-type: none"> REMOVE & REDISTRIBUTE SEDIMENT WHEN BUILDS UP IN THE SILL FENCE
INLET PROTECTION	DAILY AFTER EACH RAIN	<ul style="list-style-type: none"> REMOVE TO FIGURES 3A1, 5A1.2.2, & 5A.1 WITH NEW YORK STANDARD SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL
TEMPORARY SWALE (IF REQUIRED)	WEEKLY AFTER EACH RAIN	<ul style="list-style-type: none"> IMMEDIATELY REMOVE AND RESTORATION VEGETATING FOR CLOSURE AS REQUIRED
		<ul style="list-style-type: none"> REPAIR ANY SWALE AND SURROUNDING AREA FOR BELLING & REPAIR AS REQUIRED WITH THE PLACEMENT OF ADDITIONAL TOPSOIL, THEN SEEDING AND MULCHING AS UNLESS IN FIGURE NO. 5A.2 OF THE NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL
SEDIMENT SUMP PIT (IF REQUIRED)	DAILY AFTER EACH RAIN	<ul style="list-style-type: none"> CONFIRM THAT STORMWATER IN THE PITS IS CLEAN AND FREE OF TURBIDITY PERIODICLY CLEAN PUMPING EQUIPMENT TO PREVENT CLOGGING REMOVE TOUGHLY ADHERED PARTICULATE AND DEBRIS FROM THE STORMWATER IN THE PIT IS CLEAN EXPOSED SEDIMENT AND DEBRIS SHOULD BE REMOVED TO THE CLOSURE'S STORE AS NEEDED TO ENSURE PROPER FUNCTION AND TO PREVENT CLOGGING

PROBLEM AND SEGMENT CONTROL MEASURE	INSPECTION/MAINTENANCE INTERVALS	INSPECTION/MAINTENANCE REQUIREMENTS
VEGETATED SHALE	MONTHLY	<ul style="list-style-type: none"> • CHECK THAT CONTRIBUTING AREA IS CLEAN OF DEBRIS. • CONTROL VEGETATION IS ADEQUATE TO PREVENT EROSION. • CHECK FOR RILLING/EROSION AND REPAIR AS NEEDED. • CONTROL DRAINING OCCURS BETWEEN STORMS.
SURFACE/ SUBGRADE STORMWATER MANAGEMENT DRAINAGE FACILITY	ANNUALLY + AFTER MAJOR STORMS	<ul style="list-style-type: none"> • CHECK LEVEL OF SEDIMENT AND DEBRIS ACCUMULATED WITHIN THE SYSTEM. • CHECK STRUCTURAL INTEGRITY OF SYSTEM PIPES, STRUCTURES, ETC. • CHECKING, BULGING OR DISPLACEMENT OF SYSTEM PIPES, STRUCTURES, ETC. • CORRECT ALL INLETS AND OUTLETS/ STRUCTURES/PIPPES ARE OPERATING PROPERLY.
DRAIN INLETS AND TRENCH DRAINS	MONTHLY	<ul style="list-style-type: none"> • CHECK FOR BLOCKAGE AND/OR EROSION AT TOP OF EACH INLET. • REMOVE DEBRIS AS NECESSARY. • CHECK FOR SEDIMENT AND DEBRIS COLLECTED WITHIN SAMPS AND CLEAN UP AS NECESSARY.
NATIVE STONE WALL	ANNUALLY + AFTER MAJOR STORMS	<ul style="list-style-type: none"> • CHECK FOR EROSION AND/OR DAMAGE AND REPAIR AS NECESSARY.
STORMWATER SURFACE/ SUBGRADE RETENTION FACILITY	SEMI-ANNUALLY + AFTER MAJOR STORMS (SEE MAINTENANCE GUIDELINES IN APPENDIX G)	<ul style="list-style-type: none"> • CHECK LEVEL OF SEDIMENT ACCUMULATED WITHIN THE SYSTEM. • CHECK FOR EROSION OF THE SLOPE ROW THROUGH THE ADJACENT AREA. • CHECK FOR EROSION OF 10 TO 30% CLEAN OUT UTILIZING A HIGH PRESSURE WATER HOSE TO SLOPE AND SURFACED SEDIMENTS. • FLUSH ALL SEDIMENT TO ACCESS MAINTENANCE AND REMOVE USING A VACUUM TRUCK.
GOOD WATER QUALITY STRUCTURE	QUARTERLY + AFTER MAJOR STORMS (SEE MAINTENANCE GUIDELINES IN APPENDIX G)	<ul style="list-style-type: none"> • OPEN ACCESS COVER FOR VISUAL CHECK OF DEBRIS. • MEASURE DISTANCE FROM THE STANDING WATER TO THE SEDIMENT LINE. • MEASURE STOKING ROW TYPICAL IF EROSION OF THE SEDIMENT LINE. • VACUUM TRUCK TO REMOVE DEBRIS COMES TO CLEAN OUT THE STUMP. • SORTEN THROUGH BOTH ACCESS LOCATIONS TO REMOVE DEBRIS. • VACUUM TRUCK TO REMOVE DEBRIS COMES TO CLEAN OUT THE STUMP. • WATER LAYER OF OIL SEDIMENT, TRASH, ETC. THE SCREEN MUST BE POWERWASHED TO DISBURSE IT TO FILL OF TRASH AND DEBRIS.
POROUS PAVEMENT	MONTHLY & AS NEEDED	<ul style="list-style-type: none"> • ENSURE THAT PAVING AREA IS CLEAN OF DEBRIS. • ENSURE THAT PARKING DEBRIS BETWEEN STORMS. • ENSURE THAT THE AREA IS CLEAN OF SEDIMENTS. • MOW UPLAND AND ADJACENT AREA AND SEAL BARE AREAS. • VACUUM SWEEP FREQUENTLY TO PREVENT SURFACE CLOG OF SEDIMENTS. • INSPECT THE SURFACE FOR DETRIORATION OR SPALLING.
	QUARTERLY	
GREEN ROOF	SPRING	<ul style="list-style-type: none"> • ANNUAL SOIL, TEST BY REMOVING AND ANAL SOIL QUANTITIES AND SEND TO A LABORATORY FOR NUTRIENT CONTENT, ETC. • BEGON BIWEEKLY NEED INSPECTION REMOVAL. • JUSTICIALLY APPLY PHOSPHORUS FERTILIZER IF NEEDED BASED ON AN ANNUAL SOIL TEST RESULT. • BIWEEKLY CHECK FOR DISPLACED SOIL. • INSPECT ROOF DRAINS, REMOVE DEBRIS AND CHECK FOR PESTS.
	SUMMER	<ul style="list-style-type: none"> • CONTINUE BIWEEKLY NEED INSPECTION AND REMOVAL. • CONTINUE BIWEEKLY INSPECTION FOR DISPLACED SOIL, INSPECT ROOF DRAINS REMOVE DEBRIS AND CHECK FOR PESTS. • IRRIGATION MAY BE REQUIRED EVERY 3 TO 4 WEEKS DURING PROLONGED, DRY AND DRY WEATHER.
	FALL	<ul style="list-style-type: none"> • CONTINUE BIWEEKLY NEED INSPECTION AND REMOVAL. • CONTINUE BIWEEKLY INSPECTION FOR DISPLACED SOIL, INSPECT ROOF DRAINS REMOVE DEBRIS AND CHECK FOR PESTS.
	WINTER	<ul style="list-style-type: none"> • REMOVE SNOW AS NEEDED FROM ACCESS WALKWAYS.

1. THE USE OF GREEN STREET DURING CONSTRUCTION AND FOR CONSTRUCTION EQUIPMENT ACCESS SHALL BE MINIMIZED TO THE EXTENT POSSIBLE.
2. NO CONSTRUCTION RELATED VEHICLES OR EQUIPMENT SHALL ENTER UPON PRIVATE PROPERTY WITHOUT THE PRIOR APPROVAL OF THE PROPERTY OWNER.
3. TWO-WAY TRAFFIC ON ALL PUBLIC ROADS SHALL BE MAINTAINED THROUGHOUT THE DURATION OF CONSTRUCTION, UNLESS PARTIAL ROAD CLOSURES ARE NECESSARY AND ARE PREVIOUSLY APPROVED BY THE TOWN ENGINEER SUPERINTENDENT WITH APPROPRIATE FLAGMEN AND SIGNAGE PROVIDED.
4. NO MACHINERY, EQUIPMENT OR VEHICLES SHALL BE PARKED OR STORED WITHIN ANY RIGHT-OF-WAY DURING THE HOURS OF OPERATION, PARKING OF CONSTRUCTION WORKERS VEHICLES AND DEBRIS SHALL NOT BE PERMITTED ON ROADWAY.
5. SIGNS READING "NO CONSTRUCTION VEHICLES BEYOND THIS POINT" SHALL BE PLACED AT THE POINTS WHERE PRIVATE DRIVEWAYS INTERSECT THE TOWN RIGHT-OF-WAY.
6. THE LIMITS OF RE-PAVING GREEN STREET SHALL BE DETERMINED BY THE TOWN HIGHWAY SUPERINTENDENT AND TOWN ENGINEER FOLLOWING THE INSTALLATION OF DRAINAGE INFRASTRUCTURE AND FOLLOWING THE REPAIR OF GREEN STREET.

SEDIMENT TRAP INFORMATION								
TRAP NUMBER	TRAP TYPE	DRAINAGE AREA (ACRES)	STORAGE CAPACITY (CUBIC FEET)	STORAGE PROVIDED (CUBIC FEET)	OUTLET LENGTH (FEET PER BARREL)	STORAGE DEPTH BELOW OUTLET (FEET)	RISER/OUTLET ELEVATION	EMBANKMENT HEIGHT AND ELEVATION
1.	PIPE OUTLET	3.17	11,412	13,808	24" DIA. RISER, 21" DIA. BARREL	2.5	168.50	4', 168.00
2.	PIPE OUTLET	1.46	5,256	5,325	18" DIA. RISER, 15" DIA. BARREL	2.5	210.50	4', 212.00

PHASE 2
STABILIZED
INSTRUCTION
ENTRANCE
(TYPICAL)

NEW YORK STATE

PHASE 2
STABILIZED
CONSTRUCTION
ENTRANCE

NOTE:
THE OWNER/OPERATOR RESPONSIBLE FOR INSPECTION
AND MAINTENANCE AS OUTLINED ABOVE AND IN THE
STORMWATER POLLUTION PREVENTION PLAN IS:
CELEBRITY AUTO OF WESTCHESTER, LLC
MR. TOM MAOJ
130 ROUTE 10
WHIPPANY, NJ 07981
PHONE: (973) 727-7016
FAX: (973) 319-1013
EMAIL: TMAOJ@CELEBRITYAUTOROUTE10.COM

PHASE 1 EROSION CONTROL MEASURES TO REMAIN AND BE MAINTAINED IN PHASE 2 FOR ADDED PROTECTION.

PHASE 1 EROSION CONTROL MEASURES TO REMAIN AND BE MAINTAINED IN PHASE 2 FOR ADDED PROTECTION

SILT FENCE

PHASE 2 PLAN

MERCEDES BENZ OF GOLDENS BRIDGE

TOWN OF LEWISBORO NY
NYS ROUTE 22

Drawn: SS Approved: A

Date: 05/01/2024

16124-SITE	PHASE 2	PHASIN
------------	---------	--------

Drawing No: C 402

0 402
